



HYP BATT

Hyper powered vessel battery charging system

Document Title	Hyper vessel charging DEMO
Document type and number	Deliverable 3.5

Primary Author(s)	Thomas Gerrits HELIOX BV Marcello Maccarini HELIOX BV
Document Version Status	2.0 final
Distribution level	SEN – SENSITIVE

Project Acronym	HYPOBATT
Project Title	Hyper Powered vessels battery charging system
Project website	WWW.HYPOBATT.EU
Project Coordinator	Endika Bilbao IKE ebilbao@ikerlan.es
Grant agreement number	101056853

Date of deliverable: [30.09.2025]

Date of submission: [30.09.2025]



Funded by the European Union

Funded by the European Union. Views and opinions expressed are however those of the author(s) only and do not necessarily reflect those of the European Union or the European Climate, Infrastructure and Environment Executive Agency (CINEA). Neither the European Union nor the granting authority can be held responsible for them.

Copyright © all rights reserved. This document or any part thereof may not be made public or disclosed, copied or otherwise reproduced or used in any form or by any means, without prior permission in writing from the HYPOBATT Consortium. Neither the HYPOBATT Consortium nor any of its members, their officers, employees, or agents shall be liable or responsible in negligence or otherwise for any loss, damage or expense whatever sustained by any person as a result of the use, in any manner or form, of any knowledge, information or data contained in this document, or due to any inaccuracy, omission or error therein contained.



CONTRIBUTORS

	Name Organisation	Date
Document Manager	T. Gerrits Heliox	2025-09-02
Contributor 1	M. Maccarini Heliox	2025-09-02
Contributor 2	J. Gerrist Heliox	2025-09-04
Contributor 3	D. Sützen Imecar (reviewer)	2025-09-09

DOCUMENT HISTORY

Document Version	Date	Author Organization	Description
0.1	2025-09-02	T. Gerrits Heliox	Initial version
1.0	2025-09-02	T. Gerrits Heliox	Edited version
2.0	2025-09-30	T. Gerrits Heliox	Final version – Submitted to EC

Approval Status			
	Organisation Name	Checked By	Approved
WP Leader Approval	Heliox	T. Gerrits	Date:
			Signature: Thomas Gerrits



TABLE OF CONTENTS

1. EXECUTIVE SUMMARY	5
2. images of the demonstrator	6
2.1 Baseframe	6
2.2 Multi-MW charger.....	6
2.3 Dry cooler	7
2.4 Assembled combination for DEMO	8
2.5 Internal components in MW charger container	10
2.6 DC outlet dispenser	14
3. Functional performance verification	16
3.1 Functional testing verification.....	16
3.2 Power conversion testing	16
Appendix A – The functional performance verification of the HV section of the container (in Dutch).....	17
Appendix B - The functional performance verification of the Container LV section (In Dutch)	18
Appendix C – Declaration of Conformity (in Dutch)	19
Appendix D - Inspection report of the Container (In Dutch).....	20



LIST OF FIGURES

Figure 1 placement of baseframe at testing site..... 6

Figure 2 placement of the multi-MW charger on the baseframe..... 6

Figure 3 placement of the dry cooler on top of the baseframe and multi-MW charger..... 7

Figure 4 assembled combination of baseframe, multi-MW charger container and dry cooler on top **viewpoint:** left; LV DC output side with cable connections behind bottom doors, right: AFE2 power conversion and protection compartment doors, far-right: bottom grid-iron for transformer air-intake..... 8

Figure 5 assembled combination of baseframe, multi-MW charger container and dry cooler on top **viewpoint:**left image: left side: MV switchgear doors, right side: AC connection for testing. Right image: left side: bottom grid-iron for transformer air-intake, right side: AFE1 power conversion and protection compartment doors..... 9

Figure 6 cooling station with left: manifold supply (top) and return (bottom), behind that the pumping station, right: heat exchanger with fans. 10

Figure 7 Mounted MV switchgear set and MV cables installation 11

Figure 8 LV DC and control side during installation check and testing start-up 12

Figure 9 LV AC air-circuit breakers and pre-charging compartment 13

Figure 10 external cabinet of the DC outlet dispenser (glands grouped per DC-field, to be connected with dedicated tooling due to small mutual distances). 14

Figure 11 internal control section of the DC outlet dispenser (missing the central controllers still)..... 14

Figure 12 internal power section of the DC outlet dispenser 15

Figure 13 DC voltage and current ramp-up behaviour of the 2x30kW connected to SKID capacitor bank, changing the DC link voltage in 10% up. 16



1. EXECUTIVE SUMMARY

This document encompasses the proof material to show the implementation of the Hyper vessel charging DEMO. Within the WP3 scope, 4 main items have been realized in accordance with the system architecture D3.1. The implemented hardware will be shown in the following sections, i.e.:

- **Container base frame:** for cable management and ease of installation
- **Multi-MW charger** (D3.4): the power conversion equipment
- **Dry cooler:** to retrieve hot air from the charger and release it to the ambient
- **DC outlet dispenser:** to perform charging steps and communicate between the charger and the Frisia E-I electric catamaran vessel (EV)

The combination of container base frame, multi-MW charger, and dry cooler are visualized as one assembled set, equal to the composition that will be used during the DEMO in WP5.

Additionally, an installation manual is being developed based on the learnings experienced during placement of the system, and on discussions with the WP5 use-case partners. As agreed with the project team, the installation manual is to be added as an appendix to D3.4. At the point of writing, this manual focusses on the high-level placement on site, rather than the details of connections. The latter needs input from functional testing as is planned for Q4 2025.

Finally, in the last chapter, the functional verification and power circulation performance testing is explained with some results and pictures. Therein an explanation is given on the first results gained.

2. IMAGES OF THE DEMONSTRATOR

2.1 Baseframe



Figure 1 placement of baseframe at testing site

2.2 Multi-MW charger



Figure 2 placement of the multi-MW charger on the baseframe



2.3 Dry cooler



Figure 3 placement of the dry cooler on top of the baseframe and multi-MW charger

2.4 Assembled combination for DEMO



Figure 4 assembled combination of baseframe, multi-MW charger container and dry cooler on top
viewpoint: left; LV DC output side with cable connections behind bottom doors, right; AFE2 power conversion and protection compartment doors, far-right: bottom grid-iron for transformer air-intake.



*Figure 5 assembled combination of baseframe, multi-MW charger container and dry cooler on top
viewpoint: left image: left side: MV switchgear doors, right side: AC connection for testing. Right image:
left side: bottom grid-iron for transformer air-intake, right side: AFE1 power conversion and protection
compartment doors.*

2.5 Internal components in MW charger container



Figure 6 cooling station with left: manifold supply (top) and return (bottom), behind that the pumping station, right: heat exchanger with fans.



Figure 7 Mounted MV switchgear set and MV cables installation



Figure 8 LV DC and control side during installation check and testing start-up



Figure 9 LV AC air-circuit breakers and pre-charging compartment

2.6 DC outlet dispenser



Figure 10 external cabinet of the DC outlet dispenser (glands grouped per DC-field, to be connected with dedicated tooling due to small mutual distances).



Figure 11 internal control section of the DC outlet dispenser (missing the central controllers still)



Figure 12 internal power section of the DC outlet dispenser

3. FUNCTIONAL PERFORMANCE VERIFICATION

3.1 Functional testing verification

- The functional performance verification of the HV section is detailed in Appendix A (in Dutch)
- The functional performance verification of the Container LV section is detailed in Appendix B (in Dutch)
- Declaration of Conformity of the Container is detailed in Appendix C (in Dutch)
- Inspection report of the Container is detailed in Appendix D (in Dutch)

3.2 Power conversion testing

The first results regarding power conversion testing are depicted in the following pictures. It proved to be very complex to start the 3 MW system from the weak grid connection available (63 A). This is due to the LC-filter in the power conversion section, which leads to a large reactive current flowing in between of the AFE drive and the building installation. Principally, a much larger grid connection is needed for that. As a result, the testing needed to be relocated to another site which allowed for the use of a 400 A AC connection (shown in Figure 5, left image) replacing the 63 A in the earlier test site.




Figure 13 DC voltage and current ramp-up behaviour of the 2x30kW connected to SKID capacitor bank, changing the DC link voltage in 10% up.



APPENDIX A – THE FUNCTIONAL PERFORMANCE VERIFICATION OF THE HV SECTION OF THE CONTAINER (IN DUTCH)



APPENDIX B - THE FUNCTIONAL PERFORMANCE VERIFICATION OF THE CONTAINER LV SECTION (IN DUTCH)



APPENDIX C – DECLARATION OF CONFORMITY (IN DUTCH)



APPENDIX D - INSPECTION REPORT OF THE CONTAINER (IN DUTCH)